



NEW ENTRY LOCKS

REMOVE AND REPLACE EXISTING AWNING.

SCRAPE AND PATCH EXISTING DEFECTS AS REQ. PAINT.

NEW DELIVERY DOOR. DEMO EXISTING BLOCK PATCH AS REQ.

REMOVE EXISTING WINDOWS, BLOCK IN TO MTCH.

1 MAIN FLOOR
A1 1/4" = 1'-0"

NOTE: KITCHEN EQUIPMENT TO BE PROVIDED BY SUPPLIER.
PRELIMINARY BUDGET BIDS ONLY - NOT FOR CONST.
FINISHES WILL BE DETERMINED AND COMPLETE ARCH. PLANS PROVIDED AT A LATER DATE.
DIMENSIONS ARE NOT VERIFIED AND FOR BIDDING PURPOSES ONLY.
ALL CONDITIONS MUST BE INSPECTED AND VERIFIED TO MEET CODES.
OFFICES UPSTAIRS WILL BE IN ANOTHER PHASE

PROVIDE ALLOWANCE FOR EXTERIOR FACELIFT AND DESIGN TED.
BOOTH AND FURNITURE MATERIAL AND DESIGN TO PROVIDED BY OWNER FOR BID PURPOSES.
PROVIDE PAINT FOR ENTIRE SPACE.
PATCH EXISTING FLOORING UNLESS OTHERWISE NOTED.
CALL OWNER OR DESIGNER FOR CLARIFICATION. ASSUMPTIONS WILL NOT BE ACCEPTED.

RE-SLOPE EXISTING CONC. TO FIX WATER FLOW PROBLEM.